

**SECTION 00 41 43**

**BID FORM**

**OWNER:** City of Oak Ridge North  
27424 Robinson Road  
Oak Ridge North, Texas 77385  
Attn: Joe Sherwin, P.E.

**Project Name:** Woodson Road and Blueberry Hill Drive Roadway Improvements  
**Project No:** 12700

**BIDDER:** \_\_\_\_\_

**1.0 OFFER**

- A. Total Bid Price:** Having examined the Project location and all matters referred to in Bid Documents for the Project, we, the undersigned, offer to enter into a Contract to perform the Work for the Total Bid Price shown on the signature page of this Document.
- B. Period for Bid Acceptance:** This offer is open to acceptance and is irrevocable for 60 days from Bid Date. The period for bid acceptance may be extended by mutual written agreement of the OWNER and BIDDER.
- C. Addenda:** All Addenda have been received. Modifications to Bid Documents have been considered and all related costs are included in the Total Bid Price.

BIDDER acknowledges receipt of the following ADDENDA:

Addendum No.: _____	Date: _____	Addendum No.: _____	Date: _____
Addendum No.: _____	Date: _____	Addendum No.: _____	Date: _____
Addendum No.: _____	Date: _____	Addendum No.: _____	Date: _____
Addendum No.: _____	Date: _____	Addendum No.: _____	Date: _____

**D. Bid Supplements:** The following documents are attached:

- Security Deposit (as defined in Document 00 21 13 – Instructions to BIDDERS)
- Others as listed: \_\_\_\_\_  
\_\_\_\_\_



B.6	<b>Specification 02 41 13</b> Remove and dispose of the existing concrete top with MH cover on the north side of Woodson Road at Sta. 3+21 to prepare for proposed grate inlet as shown on plans and as specified.	LS	1	\$ _____	\$ _____
B.7	<b>Specification 02 41 13</b> Remove and dispose of the existing 18" concrete culvert pipe under driveway at Sta 3+21 as shown on plans and as specified. Culvert is 38 LF.	LS	1	\$ _____	\$ _____
B.8	Provide and install Type A grate inlet at Sta 1+29 including any required cutting into the existing 60" storm drain, pouring cast in place concrete base, concrete riser section with grate and frame as shown on plans and as specified.	LS	1	\$ _____	\$ _____
B.9	Provide and install Type A grate inlet at Sta 3+21 (north) including any concrete work to accommodate concrete riser sections with grate and frame as shown on plans and as specified.	LS	1	\$ _____	\$ _____
B.10	Provide and install Type A grate inlet at Sta 3+21 (south) including any required cutting into the existing 24" storm drain, pouring cast in place concrete base, installing concrete riser sections with grate and frame as shown on plans and as specified.	LS	1	\$ _____	\$ _____
B.11	Provide and install 18" RCP culvert piping along Woodson Road for the south driveway at STA 3+21 and at Blueberry Hill Drive as shown on plans and as specified.	LF	48	\$ _____	\$ _____
B.12	<b>Specification 32 11 13.13 and 32 11 13.19</b> Subgrade Stabilization. Includes grading in ROW, removal of excess soil as required, and chemically modify soil per a geotechnical recommendation. See bid item B.29 (6" min per City detail) along the north side of Woodson Road and Blueberry Hill as part of the roadway widening work and compact to 95% of standard proctor density as shown on plans and as specified.	SY	752	\$ _____	\$ _____
B.13	<b>Specification 32 13 13 and 32 16 13</b> Provide and install 8" steel reinforced concrete paving on Woodson Road at I-45 frontage as shown on plans and as specified.	SY	85	\$ _____	\$ _____

B.14	<b>Specification 32 13 13 and 32 16 13</b> Provide and install 6" steel reinforced concrete paving for south driveway at Sta 2+00 as shown on plans and as specified.	SY	77	\$ _____	\$ _____
B.15	Provide and install 7" Type B asphaltic base material including prime coat on Woodson Road and Blueberry Hill Drive as shown on plans and as specified. See typical road section for flexible base placement and required level up on existing base.	SY	665	\$ _____	\$ _____
B.16	<b>Specification 32 12 16</b> Provide and install 2" Type D Asphalt paving, including tack coat, on Woodson Road and associated driveways and at Blueberry Hill Drive as shown on plans and as specified.	SY	1720	\$ _____	\$ _____
B.17	Regrade swale on north side of Woodson Road to inlet at Sta 3+21 and roadside ditch from Sta 2+25 to Sta 4+00 on south side of Woodson Road to culverts that drain to proposed inlet around Sta 3+21 and ditches at Blueberry Hill Drive as shown on plans and as specified.	LF	190	\$ _____	\$ _____
B.18	<b>Specification 02 41 13</b> Remove, salvage, and reset existing stop sign with street names at the intersection of Woodson Road and I-45 Frontage as shown on plans and as specified.	LS	1	\$ _____	\$ _____
B.19	Provide and install stop Signs at driveways tying into Woodson Road as shown on plans and as specified.	EA	2	\$ _____	\$ _____
B.20	<b>Specification 32 16 13</b> Provide and install materials to build two ADA compliant handicapped ramps including detectable warning (truncated dome pavers or other approved device) in the I-45 ROW as shown on plans and as specified.	EA	2	\$ _____	\$ _____
B.21	<b>Specification 32 16 13</b> Provide and install 6" concrete curbing at I-45 frontage road as shown on plans and as specified.	LF	120	\$ _____	\$ _____
B.22	<b>Specification 31 22 19</b> Final grading on north side of Woodson Road from I-45 to first driveway along the ROW. Grade to 3:1 max slope within the Woodson Road ROW and create a drainage path or swale to drain runoff from the roadway to the proposed inlet at Sta 1+29 as shown on plans and as specified.	LS	1	\$ _____	\$ _____

B.23	<b>Specification 32 92 13 or 32 92 23</b> Hydromulch/Sod all disturbed areas on Woodson Road and Blueberry Hill Drive as shown on plans and as specified. Sod to be laid along ROW in front of Whiskey Cake Restaurant (~4 pallets sod, 0.25 acre of hydromulch total both work areas).	LS	1	\$ _____	\$ _____
B.24	<b>Specification 01 57 13</b> Provide and install materials for erosion control fencing and inlet protection barriers as shown on plans and as specified. Includes installation, maintenance during project as required, and removal.	LS	1	\$ _____	\$ _____
B.25	<b>Specification 01 55 26</b> Traffic Control. Provide, install, and remove at end of project, all Traffic Control signs, PCMS dynamic signs, flaggers, cones, barricades, etc. to provide a full traffic control plan as shown on the plans and as specified.	LS	1	\$ _____	\$ _____
B.26	Provide and install junction box at the intersection of Blueberry Hill Dr. and Woodson Road including all dirtwork, compaction, cement stabilized sand, or other incidentals as shown on plans and as specified	EA	2	\$ _____	\$ _____
B.27	Provide and install 24" Safety End Treatments, including compaction, cement stabilized sand, or other incidentals as shown on plan and as specified.	EA	2	\$ _____	\$ _____
B.28	Provide and install 18" Safety End Treatments, including compaction, cement stabilized sand, or other incidentals as shown on plan and as specified.	EA	2	\$ _____	\$ _____
B.29	Lab testing for materials and compaction and subgrade stabilization. Contractor to use approved testing lab. Follow contractor's Geotech recommendations for subgrade stabilization based on in-situ soil conditions	LS	1	\$ _____	\$ _____
<b>TOTAL BASE BID:</b>				\$ _____	

Footnotes for Basic Unit Price Table and Extra Unit Price Table:

- (1) Fixed Unit Price determined prior to Bid. Cannot be adjusted by the BIDDER.
- (2) Minimum Bid Price determined prior to Bid. Can be increased by the BIDDER by crossing out the Minimum and noting revised price on the line above.
- (3) Maximum Bid Price determined prior to Bid. Can be decreased by BIDDER by crossing out the Maximum and noting revised price on the line above.
- (4) Fixed Range Unit Price determined prior to Bid. Unit Price can be adjusted by BIDDER to any amount within the range defined by crossing out prices noted and noting revised price on the line above.

**C. EXTRA ITEMS UNIT PRICE TABLE:**

Item No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total
C.1	Provide and install Tensar Glaspave 25 between base material and 2" Type D surface course on Woodson Road (Sta 0+94.60 to Sta 5+56.23) including all incidentals as shown on paving detail and as specified	SY	1,325	\$ _____	\$ _____
C.2	Provide and install surface mount delineators along Woodson Road per the striping plan. Refer to TXDOT drawing D&OM (2)-15 for detail on surface mounted delineator type as shown on striping plan and as specified. Include all incidental items for installation	EA	6	\$ _____	\$ _____
<b>TOTAL EXTRA ITEMS:</b>				\$ _____	

**D. CASH ALLOWANCE TABLE:**

Item No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total
D.1	Cash Allowance for Contingency items. Used only with City and Engineer approval	CA	1	\$ 15,000.00	\$ 15,000.00
<b>TOTAL CASH ALLOWANCE:</b>				\$ 15,000.00	

**F. BID PRICE SUMMARY:**

1. **TOTAL BASE BID** \$ \_\_\_\_\_  
(Add totals from Sections A and B)
  
2. **TOTAL BASE BID WITH CASH ALLOWANCE** \$ \_\_\_\_\_  
(Add totals from Sections A, B, and D)
  
3. **TOTAL BASE BID WITH CASH AND EXTRA ITEMS** \$ \_\_\_\_\_  
(Add totals from Sections A, B, C and D)

4.0

**SIGNATURES:** By signing this Document, I agree that I have received and reviewed all Addenda and considered all costs associated with the Addenda in calculating the Total Bid Price.

**BIDDER:** \_\_\_\_\_  
(Print or type full name of proprietorship, partnership, corporation, or joint venture.\*)

**\*\*By:** \_\_\_\_\_  
Signature Date

**Name:** \_\_\_\_\_  
(Print or type name) Title

**Address:** \_\_\_\_\_  
(Mailing)

\_\_\_\_\_  
(Street Address, if different)

**Telephone:** \_\_\_\_\_ **Fax:** \_\_\_\_\_

\* If Bid is a joint venture, add additional Bid Form signature sheets for each member of the joint venture.

\*\* BIDDER certifies that the only person or parties interested in this offer as principals are those named above. BIDDER has not directly or indirectly entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding.

**END OF SECTION**