


SEPTIC SYSTEM PROFILE

TBM @ NAIL IN SIDEWALK = 100.00

HORZ. 1" = 10' VERT. 1" = 2'



NOTES

- 1) SEPTIC TANK SHALL HAVE INLET AND OUTLET TEES.
- 2) OUTLET TEE SHALL HAVE A GAS BAFFLE. 3) D-BOX SHALL HAVE MINIMUM 12" INSIDE WIDTH AND 6" SUMP BELOW OUTLET INVERT.
- 4) ACCESS MANHOLES TO SEPTIC TANK SHALL BE WITHIN 6" OF FINISHED GRADE.
- 5) D-BOX OUTLET PIPES SHALL BE LEVEL A MINIMUM OF 2 FEET. 6) END CAPS ON PIPES, FOR NON-VENTED SYSTEMS.
- 7) ELEVATIONS ARE TO INVERTS UNLESS
- 8) NO OTHER WELLS OR WETLANDS OBSERVED WITHIN 200' OF SEPTIC SYSTEM.
- 9) ALL LOAM, SUBSOIL AND OTHER IMPERVIOUS MATERIAL SHALL BE REMOVED WITHIN 5 FEET OF LEACHING FACILITY. 10) FILL WITHIN 5 FEET OF LEACHING FACILITY
- SHALL MEET SPECIFICATIONS OF TITLE V, 15.255(3). 11)FINISH GRADE ABOVE AND ADJACENT TO
- SYSTEM SHALL SLOPE AT LEAST 2% TO PREVENT ACCUMULATION OF SUBSURFACE WATER. 12)DISTRIBUTION BOX SHALL HAVE AN INLET
- TEE OR BAFFLE EXTENDING TO ONE INCH ABOVE THE OUTLET INVERT ELEVATION PROVIDED TO DISSIPATE THE VELOCITY OF THE INFLUENT.

SEE ATTACHED SOIL LOG

13)SEPTIC TANK SHOULD BE INSPECTED

- ANNUALLY. 14)ALL PIPES SHALL BE EITHER ASTM D-3034 (SDR35), ASTM D-2665 (SCHEDULE 40) OR AS
- 15)ALL WASTEWATER SHALL FLOW INTO THE SEPTIC TANK. WITH THE EXCEPTION OF WATERSOFTENERS/CONDITIONERS. 16)LOT LINES PLOTTED FOR SEPTIC LOCATION ONLY.
- PLOT PLAN IS NOT AN ACTUAL SURVEY. 17)NO CONSTRUCTION OF PERMANENT STRUCTURE ALLOWED OVER SEPTIC SYSTEM.

22)CALL 1-888-DIG-SAFE BEFORE STARTING SITE WORK.

18)TOPOGRAPHY SURVEY DATA APPROXIMATE 19)MAGNETIC TAPE REQUIRED OVER ALL SYSTEM COMPONENTS. 20)GAS BAFFLE REQUIRED BETWEEN THE TWO COMPARTMENTS OF TANK. 21)METAL REBAR REQUIRED AT D-BOX AND ALL CORNERS OF LEACH BED.

SITUATION:

REPAIR OF SAS AT 9 GREENWICH PLAINS ROAD. 2 BEDROOM DWELLING, NO GARBAGE GRINDER. PERC RATE AT HOLE 1 OF <2 MINUTES PER INCH. DOP = 18" TO BOTTOM PERC TEST DATE: 02/19/20 BOARD OF HEALTH WITNESS: FINN McCOOL SOIL EVALUATOR: NEIL JACKSON, CERTIFIED MAY, 1998

2 BEDROOMS @ 110 GAL

TOTAL = 220 GAL

ESTIMATED AVERAGE DAILY FLOW BASED ON 1995 TITLE 5 REGULATIONS LEACHING SYSTEM IS TO CONSIST OF A 14 FT. X 30 FT. LEACHING BED, WITH 3 DISTRIBUTION LINES, WITH A MINIMUM OF 6 INCHES OF STONE THROUGHOUT BED. DESIGN CALCULATIONS:

SOIL CLASS I $- < 2 \text{ MIN./IN} = 0.74 \text{ GAL/FT}^2$


BOTTOM AREA: $14' \times 30' = 420 \text{ FT}^2$ SIDE AREA: NOT ALLOWED IN BEDS

> $TOTAL = 420FT^2 = 310.8 GALLONS CAPACITY$ 310.8 GAL. DESIGN > 220 GAL. REQUIRED

CROSS SECTION OF LEACHING BED


@ PIPE END DO NOT SCALE REMOVE ALL TOP AND TBM @ NAIL IN SIDEWALK = 100.00 SUB SOIL FOR 5 FT IN ALL DIRECTIONS AND REPLACE WITH SELECT SAND PER 310 CMR 15.255 MIN, 9" BACKFILL Finish Ground Surface NOT INCLUDING TOP SOIL 1/8" TO 1/2" DOUBLE WASHED STONE 3/4" TO 1-1/2" DOUBLE WASHED STONE SEPARATION DISTANCE ELEVATION OF DEEP HOLE 1 = 99.54 ALL SIDES ESTIMATED HIGH WATER LEVEL = 92.04

ALL SOIL ABSORPTION SYSTEMS SHALL HAVE A MINIMUM OF ONE INSPEC OF A PERFORATED FOUR INCH PIPE PLACED VERTICALLY DOWN INTO THE NATURALLY OCCURRING SOIL OR SAND FILL BELOW THE STONE. THE P WITH A SCREW TYPE CAP AND ACCESSIBLE TO WITHIN THREE INCHES OF



GAS BAFFLE DETAIL

SYSTEM TO BE CONSTRUCTED IN COMPLIANCE WITH 310 CMR 15.000



896-6607

Belch

Engineering