2019 Westwood Development Consultants, LLC.

WARE SOLAR WARE PLANNING COMMISION PLANS


FOR

Site/Electrical Layout, Grading/Drainage/Erosion Control/Landscaping

IN

WARE, MASSACHUSETTS


LOCATION MAP



SOURCE: MAP DATA ©2017 GOOGLE (NOT TO SCALE) CONTACT INFO:

OWNER/DEVELOPER: ECOS ENERGY 222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402

CIVIL ENGINEER:
WESTWOOD PROFESSIONAL
SERVICES
12701 WHITEWATER DRIVE
SUITE 300,
MINNETONKA, MN 55343



Civil Details

18






Designed:		MF
Checked:		ΑI
Drawn:		MF
Record Drawing b	y/date:	
Revisions: # DATE	DESCRIPTION	
	-	
Prepared for:		
Frepared for.	- ~	

WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

COVER SHEET

PRELIMINARY-NOT FOR CONSTRUCTION



EXISTING LOT LINE
PROPOSED LOT LINE
PROPOSED FENCE
ACCESS ROAD EASEMENT
PROPOSED GRAVEL ACCESS ROAD
WETLAND BUFFER AREA
WETLAND DELINEATION LINE/AREA
PROPOSED AC DISTRIBUTION
18 x 2 SOLAR MODULE BOCK
MODULE SETBACK LINE
DISTURBANCE LIMIT

PROPOSED SAND FILTER

LEGEND:




937-5150 12701 Whitewater Drive, Suite Minnetonka, MN 55343 westwoodps.com



Designed:		MPG
Checked:		ADC
Drawn:		MPG
Record Drawin	g by/date:	
Revisions: # DATE	DESCRIPTION	
Prepared for:		

222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402




WARE SOLAR


MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

OVERALL SITE PLAN

PRELIMINARY-NOT FOR CONSTRUCTION



LEGEND:



CONSTRUCTION SEQUENCING NOTES:

- 1. THE CONTRACTOR SHALL PERFORM ALL TREE REMOVAL ACTIVITIES ON SITE TO ALLOW FOR BMP INSTALLATION, NO GRUBBING IS TO OCCUR DURING TREE REMOVAL, PRIOR TO BMP INSTALLATION.
- 2. ALL BMP'S IDENTIFIED ON THE PLAN SHALL BE STAKED BY A REGISTERED SURVEYOR AND INSTALLED PER PLANS PRIOR TO ANY CONSTRUCTION ACTIVITY.
- 3. AS-BUILT DRAWINGS SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT THE CONSTRUCTION OF THE PROJECT.

PROJECT FOOTPRINT REMOVAL NOTES

AREAS WITHIN THE PROJECT FENCELINE LIMITS SHALL BE CLEARED BY THE FOLLOWING METHODS:

TREE CANOPY AREAS (57.9 ACRES):

1. TREES AND VEGETATION SHALL BE CLEARED AND GRUBBED

EROSION CONTROL NOTES:

- 1. TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED BEFORE ANY SOIL DISTURBANCE.
- 2. THE AREA OF DISTURBANCE SHALL BE KEPT TO A MINIMUM. DISTURBED AREAS REMAINING IDLE FOR MORE THAN 14 DAYS SHALL BE STABILIZED.
- 3. MEASURES SHALL BE TAKEN TO CONTROL EROSION WITHIN THE PROJECT AREA. SEDIMENT IN RUNOFF WATER SHALL BE TRAPPED AND RETAINED WITHIN THE PROJECT AREA USING APPROVED MEASURES.
- 4. WETLAND AREAS AND SURFACE AREAS SHALL BE PROTECTED FROM SEDIMENT. OFF-SITE SURFACE WATER AND RUNOFF FROM UNDISTURBED AREAS SHALL BE DIVERTED AWAY FROM DISTURBED AREAS WHERE FEASIBLE OR CARRIED THROUGH THE PROJECT AREA WITHOUT CAUSING EROSION. INTEGRITY OF DOWNSTREAM DRAINAGE SYSTEMS SHALL BE MAINTAINED.
- 5. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED AFTER FINAL SITE STABILIZATION. STABILIZATION MEASURES SUCH AS HYDROSEEDING OR APPLICATION OF HAY/MULCH OR SOIL NETTING SHALL BE APPLIED PRIOR TO REMOVAL OF TEMPORARY EROSION MEASURES AND INSPECTED WEEKLY UNTIL STABILIZATION IS COMPLETE. TEMPORARY EROSION CONTROL MEASURES MAY BE REMOVED ONCE STABILIZATION OF ALL SITE SOILS HAS BEEN ACHIEVED AND WRITTEN AUTHORIZATION TO DO SO HAS BEEN PROVIDED BY THE STORMWATER AUTHORITY. TRAPPED SEDIMENT SHALL BE REMOVED IMMEDIATELY WITH TEMPORARY EROSION CONTROL METHODS AND LAWFULLY DISPOSED OF OFF-SITE. OTHER DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED WITHIN THIRTY DAYS.
- 6. DEVELOPER TO OBTAIN AN NPDES PERMIT PRIOR TO CONSTRUCTION.




one (952) 937-5150 12701 W

12701 Whitewater Drive, Suite Minnetonka, MN 55343 westwoodps.com



Designed:		MPG
Checked:		ADC
Drawn:		MPG
	1.71.4	
Record Drawir	ng by/date:	
Record Drawin	ng by/date:	
Revisions:		
Revisions:		
Revisions:		






WARE SOLAR

Prepared for:

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

> REMOVAL AND EROSION CONTROL PLAN

PRELIMINARY-NOT FOR CONSTRUCTION




Westwood

one (952) 937-5150 12701 Whitewater Drive, Sui Minnetonka, MN 55343 westwoodps.com



Designed:			M
Checked:			ΑI
Drawn:			Mi
Record Dr	awing by	//date:	
Revisions:	ATE	DESCRIPTION	
Prepared f	or.		
i iepaieu i	Oi.		

222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402





WARE SOLAR


MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY


OVERALL GRADING PLAN


PRELIMINARY-NOT FOR CONSTRUCTION





















Designed:		MI
Checked:		AI
Drawn:		MF
Record Drawing	by/date:	
Revisions: # DATE	DESCRIPTION	
	_	
	-	
Prepared for:		
·		


MINNEAPOLIS, MN 55402

WARE SOLAR

MONSON TURNPIKE ROAD HAMPSHIRE COUNTY

ROAD PROFILE - 2

PRELIMINARY-NOT FOR CONSTRUCTION



28

29

540

23


24

26

ROADWAY B (CONTINUED)

1' = 10' VERTICAL

SCALE: 1'= 50' HORIZONTAL



CUVLET CROSSING AT ROADWAY B SCALE: 1'= 0.2' HORIZONTAL 1' = 8' VERTICAL

540

30 30

WARE SOLAR

Record Drawing by/date:

Prepared for:

Revisions: # DATE DESCRIPTION

222 SOUTH 9TH STREET


MINNEAPOLIS, MN 55402

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

ROAD PROFILE - 3

westwoodps.com

PRELIMINARY-NOT FOR CONSTRUCTION



Westwood


Phone (952) 937-5150 12701

5150 12701 Whitewater Drive, Suit Minnetonka, MN 55343 westwoodps.com



Designed:		MF
Checked:		ΑI
Drawn:		MF
Record Dra	wing by/date:	
Revisions: # DA	TE DESCRIPTION	
Prepared for	or.	
r roparou re		

222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402




WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

OVERALL LANDSCAPE PLAN

PRELIMINARY-NOT FOR CONSTRUCTION






Phone (952) 937-5150 12701 Whitewater Drive, Suite 300 Minnetonka, MN 55343 westwoodps.com



	MF
	AE
	MF
by/date:	
DESCRIPTION	
_	
-	

222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402




WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

DRAINAGE PLAN

PRELIMINARY-NOT FOR CONSTRUCTION





ACCESS ROAD EASEMENT

FLOW DIRECTION ARROW

WETLAND DELINEATION LINE/AREA


Phone (952) 937-5150 12701 Whitewater Drive, Suite 300

Minnetonka, MN 55343 westwoodps.com



	AD
	MP
g by/date:	
DESCRIPTION	
_	
	ng by/date: DESCRIPTION

222 SOUTH 9TH STREET SUITE 1600 MINNEAPOLIS, MN 55402



WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

POST CONSTRUCTION DRAINAGE PLAN

PRELIMINARY-NOT FOR CONSTRUCTION

ROAD DESIGN PARAMETERS

1. ROAD MAINTENANCE CAN BE EXPECTED OVER THE LIFE OF THE PERMANENT FACILITY.

SPECIAL PROVISIONS FOR GRADING AND EROSION CONTROL

THE CONTRACTOR SHALL PROVIDE EROSION CONTROL MEASURES AS PLANNED AND SPECIFIED FOLLOWING BEST MANAGEMENT PRACTICES AS OUTLINED BY THE COMMONWEALTH OF MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION AND BEING IN CONFORMANCE WITH THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL STORMWATER PERMIT. SEE THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR EROSION CONTROL AND RESTORATION SPECIFICATIONS. UNLESS OTHERWISE NOTED OR MODIFIED HEREIN, ALL SECTIONS OF THE GENERAL CONDITIONS SHALL APPLY.

EXECUTION

. CLEARING AND GRUBBING

A. THE CONTRACTOR SHALL BE REQUIRED TO REMOVE ALL TREES, STUMPS, BRUSH, AND DEBRIS WITHIN THE GRADING LIMITS SHOWN ON THE PLANS. THE CONTRACTOR IS TO REMOVE ONLY THOSE TREES WHICH ARE DESIGNATED BY THE OWNER'S REPRESENTATIVE FOR REMOVAL, AND SHALL EXERCISE EXTREME CARE AROUND EXISTING TREES TO BE SAVED.

2. TOPSOIL STRIPPING

- A. TOPSOIL SHALL BE STRIPPED FROM ALL ROADWAY AREAS THROUGH THE ROOT ZONE. TOPSOIL SHALL NOT BE STRIPPED OUTSIDE OF THE DESIGNATED DISTURBANCE AREAS.
- B. ANY TOPSOIL, THAT HAS BEEN STRIPPED, SHALL BE RE-SPREAD OR STOCKPILED WITHIN GRADING AREAS AND/OR USED AS FILL OUTSIDE OF THE DISTURBANCE AREAS, AS DIRECTED BY THE ENGINEER.
- 3. EMBANKMENT CONSTRUCTION.
- A. EMBANKMENT CONSTRUCTION SHALL CONSIST OF THE PLACING OF SUITABLE FILL MATERIAL, AFTER TOPSOIL STRIPPING, ABOVE THE EXISTING GRADE. GENERALLY, EMBANKMENTS SHALL HAVE COMPACTED SUPPORT SLOPES OF TWO AND A HALF FEET HORIZONTAL TO ONE FOOT VERTICAL. THE MATERIAL FOR EMBANKMENT CONSTRUCTION SHALL BE OBTAINED FROM THE ACCESS ROAD EXCAVATION (SEE GEOTECHNICAL REPORT FOR RESTRICTIONS), OR ANY SUITABLE, APPROVED SOIL OBTAINED OFFSITE BY CONTRACTOR, AS DIRECTED OR APPROVED BY THE ENGINEER. THIS MATERIAL SHALL BE PLACED IN LIFTS NOT TO EXCEED 9".
- B. SIDE SLOPES GREATER THAN 2.5:1 WILL NOT BE PERMITTED, UNLESS OTHERWISE NOTED ON THE PLAN.

STORM WATER DESIGN PARAMETERS

. MAINTENANCE OF STORMWATER DEVICES SHOULD BE EXPECTED OVER THE LIFE OF THE PROJECT AND PARTICULARLY AFTER HEAVY RAINFALL EVENTS.

TESTING REQUIREMENTS

- 1. TESTING SHALL BE PERFORMED BY A DESIGNATED INDEPENDENT TESTING AGENCY.
- 2. SUBMIT TESTING AND INSPECTION RECORDS SPECIFIED TO THE CIVIL ENGINEER OF RECORD FOR REVIEW.
- A. THE ENGINEER WILL REVIEW THE TESTING AND INSPECTION RECORDS TO CHECK CONFORMANCE WITH THE DRAWINGS AND SPECIFICATIONS. THE ENGINEER'S REVIEW DOES NOT RELIEVE THE CONSTRUCTION CONTRACTOR FROM THE RESPONSIBILITY FOR CORRECTING DEFECTIVE WORK.

3. PROOF ROLLING:

A. PROOF-ROLLING SHALL BE PERFORMED IN THE PRESENCE OF THE GEOTECHNICAL ENGINEER OR QUALIFIED GEOTECHNICAL REPRESENTATIVE USING A FULLY LOADED TANDEM AXLE DUMP TRUCK WITH A MINIMUM GROSS WEIGHT OF 25 TONS OR A FULLY LOADED WATER TRUCK WITH AN EQUIVALENT AXLE LOADING. PROOF-ROLLING ACCEPTANCE STANDARDS INCLUDE NO RUTTING GREATER THAN 1.5 INCHES, AND NO "PUMPING" OF THE SOIL BEHIND THE LOADED

4. SIEVE ANALYSIS:

- A. SIEVE ANALYSIS SHALL BE CONDUCTED IN ACCORDANCE WITH AASHTO T27
- 5. PROCTOR:
- A. PROCTORS SHALL BE DETERMINED IN ACCORDANCE WITH ASTM D-1557
- 6. ATTERBERG LIMITS:
- A. ATTERBERG LIMITS SHALL BE DETERMINED IN ACCORDANCE WITH AASHTO T89 AND T90
- 7. MOISTURE DENSITY (NUCLEAR DENSITY):
- A. MOISTURE DENSITY TESTING SHALL BE DONE IN ACCORDANCE WITH AASHTO T310

SUBGRADE COMPACTION, TEST ROLLING AND AGGREGATE BASE COMPACTION

1. FILL MATERIAL:

- A. SOILS USED AS FILL MATERIAL SHALL BE TESTED FOR GRAIN SIZE ANALYSIS, MOISTURE CONTENT, ATTERBERG LIMITS ON FINES CONTENT, AND PROCTOR TESTS (MODIFIED DRY MAXIMUM DENSITY).
- a. FOR PLACED & COMPACTED FILLS, PROVIDE ONE COMPACTION TEST PER LIFT FOR EVERY 1000 FT OF ROAD LENGTH. INCLUDE THE LOCATION, DRY DENSITY, MOISTURE CONTENT, AND COMPACTION PERCENT BASED ON MODIFIED PROCTOR MAXIMUM DRY DENSITY.
- B. IN ROADWAY CUT AREAS, OR WHERE EMBANKMENT CONSTRUCTION REQUIRES LESS THAN 12 INCHES OF FILL PLACEMENT, COMPACT TO A MINIMUM OF 95 PERCENT OF THE MATERIAL'S MODIFIED PROCTOR MAXIMUM DRY DENSITY.

2. COMPACTED SUBGRADE:

- A. THE ENTIRE SUBGRADE SHALL BE PROOF-ROLLED PRIOR TO THE PLACEMENT OF THE AGGREGATE BASE TO IDENTIFY AREAS OF UNSTABLE SUBGRADE.
- B. IF PROOF ROLLING DETERMINES THAT THE SUBGRADE STABILIZATION CANNOT BE ACHIEVED, THE FOLLOWING ALTERNATIVES WILL BE IMPLEMENTED:
- a. REMOVE UNSUITABLE MATERIAL AND REPLACE WITH SUITABLE EMBANKMENT.
- b. SCARIFY, DRY, AND RECOMPACT SUBGRADE AND PERFORM ADDITIONAL PROOF ROLL.
- c. INCREASE ROAD BASE THICKNESS.
- C. PROVIDE 1 MOISTURE DENSITY COMPACTION TESTS FOR EVERY 1000 L.F. OF ROAD LENGTH. COMPACTED SUBGRADE MUST BE COMPACTED TO A MINIMUM OF 95% MODIFIED PROCTOR MAXIMUM DRY DENSITY AT ±3% OF OPTIMUM MOISTURE CONTENT FOR COHESIVE SOILS.

3. AGGREGATE BASE:

- A. AGGREGATE BASE SHALL BE PROOF-ROLLED OVER THE ENTIRE LENGTH. PROVIDE 1 SIEVE ANALYSIS PER 2500 CY OF ROAD BASE PLACED.
- a. IF PROOF ROLLING DETERMINES THAT THE ROAD IS UNSTABLE, ADDITIONAL AGGREGATE SHALL BE ADDED UNTIL THE UNSTABLE SECTION IS ABLE TO PASS A PROOF ROLL.

ENERAL NOTES:

- THE PLANIMETRIC FEATURES, GROUND SURFACE CONTOURS ON A DTM SURFACE PROVIDED BY NOAA.
 NO GRADING OR SOIL DISTURBANCE IS PERMITTED OUTSIDE OF THE GRADING LIMITS IDENTIFIED ON THE PLANS.
- 3. GRADE ALL PROPOSED ROADS TO THE SLOPES PROPOSED ON THE PLANS.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. CONSTRUCTION ACTIVITIES SHALL NOT BLOCK THE NATURAL OR MANMADE CREEKS OR DRAINAGE CHANNEL CAUSING RAINWATER TO POND. ADDITIONAL CULVERTS IN EXCESS OF THOSE ON THE PLANS MAY BE REQUIRED AS APPROVED BY
- THE ENGINEER.
 5. THE CONTRACTOR SHALL NOTIFY DIGSAFE AT LEAST 48 HOURS BEFORE EXCAVATION ACTIVITIES COMMENCE.

STORMWATER POLLUTION PREVENTION PLAN (SWPPP):

- 1. REFER TO THE SWPPP BOOKLET FOR SEDIMENT AND EROSION CONTROL PROCEDURES, LOCATIONS OF BMPs, DETAILS, AND INSPECTION INFORMATION.
- 2. ALL AREAS DISTURBED DURING CONSTRUCTION ACTIVITIES AND NOT COVERED BY ROAD SURFACING MATERIALS, SHALL BE SEEDED IN ACCORDANCE WITH THE SWPPP PLAN.
- TEMPORARY EROSION CONTROL SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE TEMPORARY EROSION CONTROL PLAN SHALL BE IN ACCORDANCE WITH STATE OF MASSACHUSETTS, THE EPA, AND THE SWPPP ON FILE.

LOPE STABILIZATION:

ALL AREAS DESIGNATED ON THE PLAN FOR SLOPE STABILIZATION SHALL BE GRADED AND COMPACTED, SMOOTH AND CLEAN TO THE FINISH CONTOURS SHOWN ON THE PLAN, WITH A MINIMUM OF 4 INCHES OF TOPSOIL PLACED ON THE AREA. STABILIZATION SHALL BE ACHIEVED IN ONE OF TWO MANNERS:

EITHER: 1) RIP-RAP OR: 2) SEED WITH EROSION CONTROL AND REVEGITATION MAT (ECRM)

1. PLACEMENT OF RIP-RAP
RIP-RAP SHALL CONSIST OF D50=8". BEFORE ANY RIP RAP IS PLACED, THE SURFACE TO BE COVERED SHALL BE FULLY
COMPACTED AND GRADED TO THE REQUIRED SLOPE. PLACE MIRAFI TM8 OR APPROVED EQUAL GEOTEXTILE ON SLOPE.
RIP RAP ON SLOPES SHALL NOT BE LESS THAN 12 INCHES THICK, MEASURED PERPENDICULAR TO THE SLOPE.

2. STABILIZATION WITH EROSION CONTROL AND REVEGITATION MAT (ECRM)

1) AREA MUST BE GRADED SMOOTH AND CLEAN TO FINISH GRADES, AND COMPACTED.

2) SEED AND MULCH AREA. USE SEED MIX APPROVED BY THE ENGINEER.
3) INSTALL ECRM PER MANUFACTURER'S INSTRUCTIONS, HOWEVER THESE MUST INCLUDE THE FOLLOWING MINIMUM REQUIREMENTS:

A) GRADE GROUND TO FINISH CONTOURS. REMOVE ALL ROCKS, DIRT CLODS, STUMPS, ROOTS, TRASH, AND OTHER OBSTRUCTIONS LYING IN DIRECT CONTACT WITH THE SOIL SURFACE.

B) DIG MAT ANCHOR TRENCHES (MINIMUM 12"DEEP, 6" WIDE) AT TERMINAL ENDS AND PERIMETER SIDES WHERE MAT IS TO BE INSTALLED.

C) INSTALL MAT BY ROLLING UPHILL PARALLEL TO WATER FLOW, STARTING AT TRENCH. OVERLAP ROLLS BY

EVERY 3' TO 5' ALONG OVERLAPS. DO NO STRETCH MAT. SPLICING ROLLS SHOULD BE DONE IN A CHECK SLOT.

MINIMUM OF 3". FASTEN TO GROUND WITH 18" PINS AND 1 1/2" WASHERS, OR EQUIVALENT. PIN MAT AT ENDS, AND

BACKFILL TO COVER ENDS AND FASTENERS, ROLLING MAT ACROSS BACKFILL AND PIN AGAIN. FOR MAT USE MIRAFI MIRAMAT TM8 OR EQUIVALENT.

SEEDING:

- 1. COMPOSITION OF SEED MIX CHANGES YEARLY. SEED SPECIFICATIONS MUST BE SUBMITTED TO ENGINEER 2 WEEKS PRIOR TO INSTALLATION. ALL SPECIES MUST BE NATIVE TO WORCESTER COUNTY.
- PRIOR TO INSTALLATION. ALL SPECIES MUST BE NATIVE TO WORCESTER COUNTY.

 2. RESTORED AREAS TO BE SEEDED WITH ABOVE MIX OR EQUAL (SUBJECT TO ENGINEERS APPROVAL). SEED TO BE
- LIGHTLY RAKED TO ALLOW FOR PROPER SEED/SOIL CONTACT.

 3. CONTRACTOR SHALL OVERSEED AND/OR RE-MULCH AS NECESSARY TO ESTABLISH A GOOD COVER OF VEGETATION, WHETHER DUE TO POOR INITIAL COVER, INCLEMENT WEATHER BEFORE/DURING/AFTER SEEDING, OR THE ONSET OF
- 4. RILLING, GULLIES, OR OTHER EROSION DUE TO POOR COVER SHALL BE RAKED AND/OR REFILLED AND
- REMULCH/RESEEDED.

 5. CONTRACTOR SHALL WARRANTEE SEEDING, MULCHING AND EROSION CONTROL FABRIC FOR ONE YEAR FROM THE SUBSTANTIAL COMPLETION OF THE RELEVANT AREA OF WORK.

INVASIVE SPECIES:

- ALL EQUIPMENT SHALL BE INSPECTED UPON ARRIVAL. EQUIPMENT ARRIVING WITH OBSERVABLE SOIL OR PLANT FRAGMENTS WILL BE REMOVED AND CLEANED.
- 2. HAY BALES ARE NOT BE USED ON SITE; ONLY WEED-FREE STRAW BALES ARE APPROVED.
- OFF-SITE TOPSOIL MUST BE FREE OF INVASIVE SPECIES. THE ENGINEER SHALL BE NOTIFIED OF THE TOPSOIL

JRCE 6 WEEKS BEFORE DELIVERY.	

TABLE 3: TESTING SCHEDULE SUMMARY			
LOCATION	TEST	FREQUENCY	
STRUCTURAL FILL	GRAIN SIZE ANALYSIS, MOISTURE CONTENT, ATTERBERG LIMITS ON FINES CONTENT, AND PROCTOR	1 PER MAJOR SOIL TYPE	
	MOISTURE DENSITY	1 PER 2,000 CY OR MIN. 1 PER LIFT	
COMPACTED	PROOF-ROLL	ENTIRE LENGTH	
SUBGRADE	MOISTURE DENSITY TEST (NUCLEAR DENSITY)	1 PER 1,000 FT OR MIN. 5 FOR THE SITE	
AGGREGATE BASE	PROOF-ROLL	ENTIRE LENGTH	
	SIEVE ANALYSIS	1 PER 2,500 CY	

PROJECT SIGN:

HOURS OF OPERATION:

MONDAY THRU SATURDAY: 7:00AM - 7:00 PM, WITH NO EQUIPMENT STARTING UNTIL 7:00 AM.

SUNDAY: 9:00AM - 5:00 PM WITH NO EQUIPMENT STARTING UNTIL 8:00 AM.

NO OPERATION OF MACHINERY FOR WARM UP OR MAINTENANCE OUTSIDE OF THE ABOVE HOURS.

NO CONSTRUCTION OPERATIONS TO OCCUR ON NEW YEAR'S DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, THANKSGIVING DAY, CHRISTMAS DAY.

EMERGENCY REPAIRS AND MAINTENANCE, INCLUDING SNOW PLOWING, MAY OCCUR AT ANY TIME.
WHILE SCHOOL IS IN SESSION, ALL DELIVERIES SHALL BE SCHEDULED TO AVOID SCHOOL BUS ROUTES DURING THEIR HOURS OF PICK-UP AND DROP-OFF.

OPERATIONS MUST COMPLY WITH ANY OTHER TOWN NOISE OR HOURS OF OPERATION RESTRICTIONS.

CONTACT INFORMATION:

OWNER/DEVELOPER - ECOS ENERGY 612-326-1500

ODIS - LEE JARVIS - 508-885-7500 X180 WARE POLICE - SHAWN CREVIER - 413-967-3571

WARE CONSERVATION COMMISSION - DAVID KOPACZ - 413-967-9648 X 114 CONTRACTOR -

APPROVED CERTIFICATE OF DECISION SP-2018-04 & SPR-2018-06

GENERAL

- 1. DEVELOPER WILL BE HELD TO ALL APPLICABLE STATE AND LOCAL REQUIREMENTS
- 2. PRIOR TO APPLYING FOR A CONSTRUCTION/BUILDING PERMIT, THE CONSTRUCTION BOND, IN AN AMOUNT AGREED UPON, SHALL BE PAID; PROOF TO BE SUBMITTED TO THE PLANNING BOARD. PRIOR TO BUILDING, APPLICANT SHALL MEET WITH REPRESENTATIVES OF ALL APPLICABLE BOARDS AND COMMISSIONS FOR A PRECONSTRUCTION MEETING TO DETERMINE CURRENT BEST PRACTICES
- 3. THE WARE PLANNING BOARD RESERVES THE RIGHT TO CONDUCT SITE VISITS DURING CONSTRUCTION AND UPON COMPLETION OF THE PROJECT SCHEDULED WITH THE DEVELOPER. THE PLANNING BOARD RESERVES THE RIGHT TO MODIFY THE SCREENING WITHIN REASON, AT THE COST OF THE APPLICANT
- 4. ANY MAJOR CHANGES TO THE PLANS APPROVED BY THIS PERMIT MUST BE REVIEWED BY THE DIRECTOR OF PLANNING 81 COMMUNITY DEVELOPMENT (PCD), PRIOR TO IMPLEMENTATION, TO DETERMINE IF THEY CONSTITUTE A CHANGE SIGNIFICANT ENOUGH TO REQUIRE MODIFYING THE EXISTING SPECIAL PERMIT AND ADDITIONAL PUBLIC HEARINGS. A "MAJOR CHANGE" IS A CHANGE IN THE APPROVED PROJECT THAT WOULD HAVE

THE POTENTIAL FOR SIGNIFICANT IMPACT WITH RESPECT TO §7.2.4 OF THE WARE ZONING BYLAW.

- 5. TOWN OF WARE OFFICIALS (TOWN MANAGER AND PLANNING BOARD VIA THE PCD DEPARTMENT) SHALL BE NOTIFIED BY CERTIFIED MAIL THIRTY (30) DAYS PRIOR TO ANY CHANGE OF OWNERSHIP OF THE PROPERTY, LEASE HOLDER AND/OR PLANT OPERATING COMPANY WITHIN THIRTY (30) DAYS OF SUCH NOTICE, OR AT A MUTUALLY-CONVENIENT TIME, THE NEW PARTY SHALL ARRANGE TO MEET WITH THE PLANNING BOARD TO REVIEW THE OPERATING CONDITIONS OF THE SPECIAL PERMIT, OR AS SOON AS CONVENIENT TO BOTH PARTIES; PROVIDED THAT THIS PROVISION SHALL NOT APPLY WITH RESPECT TO ANY TRANSFER OF OWNERSHIP THROUGH A SALE-LEASEBACK FINANCING ARRANGEMENT WHEREBY THE APPLICANT CONTINUES TO OPERATE THE PROJECT.
- THE SPECIAL PERMIT SHALL BE RECORDED AT THE HAMPSHIRE DISTRICT REGISTRY OF DEEDS AND A CERTIFIED COPY OF THE RECORDING PROVIDED TO THE PCD DEPARTMENT.
 THE SPECIAL PERMIT MUST BE RECORDED AT THE HAMPSHIRE DISTRICT REGISTRY OF DEEDS WITHIN 30 DAYS
- AFTER THE APPEAL PERIOD HAS ENDED, OR 30 DAYS AFTER THE DECISION ON ANY APPEAL, OR THE PERMIT SHALL BECOME VOID
- 8. WORK MUST COMMENCE WITHIN TWO (2) YEARS OF THE APPROVAL DATE BY THE BOARD OR AN EXTENSION REQUEST MUST BE fILED AT LEAST 30 DAYS PRIOR TO THE END OF THE 2-YEAR PERIOD, WITH SUCH EXTENSION APPROVAL NOT TO BE UNREASONABLY WITHHELD OR DELAYED IF THE APPLICANT CAN DEMONSTRATE GOOD CAUSE OR THAT SUCH EXTENSION WAS REQUIRED AS A DIRECT RESULT OF THE TIMELINE ACCORDING TO THE DEPARTMENT OF ENERGY RESOURCES FOR THE SOLAR MASSACHUSETTS RENEWABLE TARGET (SMART) PROGRAM OR OTHER SIMILAR PROGRAM.
- 9. ALL APPLICABLE LOCAL, STATE, AND FEDERAL PERMITS AND APPROVALS MUST BE IN PLACE PRIOR TO THE START OF CONSTRUCTION AND OPERATIONS
- 10. APPLICANT WILL COMPLY WITH ALL LAWFUL LAWS, REGULATIONS AND REQUIREMENTS OF THE TOWN OF WARE, COMMONWEALTH OF MASSACHUSETTS, AND THE UNITED STATES OF AMERICA, THE STRICTEST OF WHICH SHALL PREVAIL

BONDS/SURETIES

- 11. PRIOR TO COMMENCING OPERATION, A FINANCIAL SURETY IN THE AMOUNT OF ONE PERCENT OF THE PROJECT CONSTRUCTION COSTS (ES SUBMITTED ON THE BUILDING PERMIT APPLICATION) SHALL BE PROVIDED AS REQUIRED IN §4.8.3.H.5 OF THE WARE ZONING BYLAW.
- 12. AT THE COMPLETION OF CONSTRUCTION, A PROJECT DECOMMISSIONING BOND SHALL BE PUT INTO PLACE AT AN AGREED UPON SUM BY THE PLANNING BOARD. SALVAGE OF SOLAR PANELS SHALL NOT BE ESTIMATED INTO THE BOND.
- 13. SATISFACTORY COMPLETION OF CONSTRUCTION SHALL BE A PROJECT THAT HAS ALL MAJOR COMPONENTS IN PLACE, ALL SITE WORK COMPLETED AND ALL CONSTRUCTION PERMITS (CONSERVATION, BUILDING, ELECTRICAL, ETC.) PROPERLY CLOSED OUT OR IN COMPLIANCE WITH ALL REGULATIONS AND REQUIREMENTS

SITE CONDITIONS

14. TOP SOIL WILL NOT BE LEFT WITHOUT SEDIMENTATION CONTROLS FOR A PERIOD OF LONGER THAN THIRTY (30)

- 15. HYDRO SEEDING (OR A COMPARABLE METHOD) WILL INCLUDE A TACKIFIER IN ORDER TO ENSURE THAT THE SEED MEDIA ADHERES TO THE SOIL PARTICLES; OR, IF HYDROSEED (OR A COMPARABLE METHOD) IS NOT USED, STRAW BALES (NOT HAY), OR OTHER COMPARABLE, APPROVED CONTROLS WILL BE USED AND MAINTAINED AS
- SEDIMENTATION CONTROLS

 16. NO CHEMICAL HERBICIDES OR FUNGICIDES SHALL BE SUED ON SITE OTHER THAN THOSE APPROVED BY THE WARE CONSERVATION COMMISSION; THE PLANNING BOARD, VIA THE PLANNING & COMMUNITY DEVELOPMENT
- DEPARTMENT STAFF, SHALL BE COPIED ON APPROVED USES

 17. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR RESTORING THE PROPERTY TO A STABLE CONDITION SHOULD THE SOLAR LESSEE, CONSTRUCTION ENTITY, OPERATOR, OR ANY OTHER OPERATOR ON THE PROPERTY, FAIL
- TO COMPLETE THE PROJECT

 18. NO CONTINUOUSLY-ON LIGHTS SHOULD BE PRESENT. MOTION DETECTOR LIGHTS AT GATE AND EQUIPMENT ARE
- PERMITTED, PROVIDED THEY CAN BE PREVENTED FROM MIS-CYCLING CAUSED BY WILDLIFE
- 19. ALL FENCING, GATES, ETC. SHALL BE A DARK, EARTH TONE COLOR SUCH AS DARK GREEN, BLACK, DARK RED, ETC. AND SHALL BE MINIMALLY 6" ABOVE THE GROUND FOR WILDLIFE MOVEMENT
- 20. GLARE IMPACTING ANY ABUTTERS SHALL BE MITIGATED BY THE APPLICANT TO THE EXTENT PRACTICABLE IN COOPERATION WITH STATE AND LOCAL OFFICIALS
- 21. CONNECTION LINES SHALL BE INSTALLED UNDERGROUND VIA BORING AT SOUTHERN PART OF PROPERTY, AWAY FROM ABUTTERS
- 22. ANY NEW POLES TO BE INSTALLED WILL BE AT THE DISCRETION OF NATIONAL GRID
- 23. THERE WILL BE NO SOIL REMOVED FROM SITE
- 24. THE CONSTRUCTION AREA LIES ADJACENT TO A WATER SUPPLY PROTECTION AREA AND PRIVATE WELLS.
- THEREFORE, ALL EQUIPMENT REFUELING SHOULD OCCUR AS CLOSE TO MONSON TURNPIKE ROAD AS POSSIBLE. A SPILL KIT INCLUDING ADSORBENTS MUST BE PRESENT AT THE SITE AT ALL TIMES FOR ALL EQUIPMENT 25. NO DIESEL FUEL TRAILER TO BE USED ON SITE IN ORDER TO AVOID SPILL PREVENTION. CONTROL AND
- COUNTERMEASURE (SPCC) RULE PROBLEMS.

 26. OPERATORS MUST BE TRAINED TO REPORT AND RESPOND TO FUEL, LUBRICANT, HYDRAULIC OR OTHER
- RELEASES. A REPORTABLE SPILL IS TYPICALLY A RELEASE OF 10 OR MORE GALLONS OF A MATERIAL. CHECK THE PERTINENT MASSDEP REPORTABLE QUANTITIES LIST FOR APPLICABLE SUBSTANCES. WHEN IN DOUBT, CONTACT THE WARE FIRE DEPARTMENT

 27. IN NO CASE SHALL THE PROJECT OPERATOR ALLOW THE SITE TO CAUSE EXCESSIVE RUNOFF TO CREATE A
- DANGEROUS CONDITION ALONG THE ROADWAY, OUTSIDE OF EXTRAORDINARY STORM CONDITIONS AS EVIDENCED BY SIMILAR ISSUES IN THE ADJACENT AREAS

 28. APPLICANT UNDERSTANDS THAT THE WARE POLICE DEPARTMENT WILL NOT POLICE THEIR UNFENCED PROJECT;
- THAT SITE SECURITY IS SOLELY IN THE APPLICANT'S CARE

 29. OTHER THAN THE PROPOSED AREA OF CONSTRUCTION, THERE WILL BE NO DEFORESTATION OTHER THAN THROUGH AN APPROVED FORESTRY CUTTING PLAN.

Westwood

one (952) 937-5150

12701 Whitewater Drive, Suite 30 Minnetonka, MN 55343 westwoodps.com



Prepared for:




WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

CIVIL NOTES

PRELIMINARY-NOT FOR CONSTRUCTION



1. ROADWAY TINSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE

ACCUMULATED TO 1/3 THE HEIGHT OF THE FABRIC OR

BE DEPOSITED TO AN AREA

2. REMOVED SEDIMENT SHALL

SEDIMENT OFF-SITE AND

CAN BE PERMANENTLY

CONTOURS TO MAXIMIZE

FENCE SHALL BE WRAPPED

UPSLOPE SO THE ELEVATION

OF THE BOTTOM OF FABRIC

IS HIGHER THAN "PONDING


PONDING EFFICIENCY.

3. SILT FENCE SHALL BE

PLACED ON SLOPE

STABILIZED.

HEIGHT".




ROLLING DIP AND WATER BAR

EXISTING **EXISTING** GRADE GRADE 6"- AGGREGATE 95% COMPACTED SUBGRADE

- 1. CONTRACTOR TO SUBCUT ROADWAY TO EXISTING GRADE ELEVATION TO MAINTAIN EXISTING SITE DRAINAGE PATTERNS
- 2. IN FILL LOCATIONS CONTRACTOR TO GRADE TOE OF SLOPE TO EXISTING GRADE, AND MAINTAIN NATURAL DRAINAGE
- 3. IN CUT LOCATIONS CONTRACTOR TO CREATE DRAINAGE CHANNEL ON DOWNSTREAM SIDE, REFER TO GRADING PLANS FOR
- 4. CONTRACTOR TO COMPACT AGGREGATE TO 95% MAXIMUM DRY DENSITY. 5. THE DITCH SHOWN ABOVE IS LOCATED AT ROADWAY B FROM STATION 7+40 TO 15+31


ACCESS ROAD AND DITCH DETAIL (CUT SECTION)



1. CONTRACTOR TO SUBCUT ROADWAY TO EXISTING GRADE ELEVATION TO MAINTAIN EXISTING SITE DRAINAGE PATTERNS

- 2. IN FILL LOCATIONS CONTRACTOR TO GRADE TOE OF SLOPE TO EXISTING GRADE, AND MAINTAIN NATURAL DRAINAGE
- 3. IN CUT LOCATIONS CONTRACTOR TO CREATE DRAINAGE CHANNEL ON DOWNSTREAM SIDE, REFER TO GRADING PLANS
- 4. CONTRACTOR TO COMPACT AGGREGATE TO 95% MAXIMUM DRY DENSITY.

ACCESS ROAD DETAIL



Minnetonka, MN 55343

westwoodps.com

Westwood

Desig	gned:		MP
Chec	ked:		AD
Draw	n:		MP
Reco	rd Drawing b	py/date:	
Revis	sions:		
Revis #	sions: DATE	DESCRIPTION	
Revis #	sions: DATE	DESCRIPTION	
Revis #	sions: DATE	DESCRIPTION	
Revis	sions: DATE	DESCRIPTION	



ACCESS ROAD SLOPES.

TRENCHING DETAIL- WITHIN ARRAY FIELD

CONDUCTOR SIZING AND QUANTITIES PER TRENCH DEPENDENT ON FINAL ELECTRICAL

1. CONDUCTOR CLEARANCES DEPENDENT ON GEOTECHNICAL PARAMETERS AND

PONDING HEIGHT

5' STEEL

T-POST

STANDARD DETAIL

TRENCH WITH NATIVE BACKFILL

ELECTRICAL DESIGN

DESIGN TRENCH DIMENSIONS.

FILTER FABRIC, ATTACH

TENSILE STRENGTH

FABRIC SLICED INTO

SILT FENCE

TRENCHING SPOIL TO BE BACKFILLED

UPON CONDUCTOR INSTALLATION

SOIL WITH COMPACTED


CONDUCTOR SIZE/QTY (TBD)

PLASTIC ZIP-TIES PER

POST WITHIN TOP 8" OF

SECURELY TO UPSTREAM

SIDE OF POST WITH 3-50lb



1. DRAINAGE CHANNEL TO SAND FILTERS SHALL BE: 1.0' DEEP; 2' WIDE BOTTOM 2.5:1 SIDE SLOPES


DRAINAGE CHANNEL NOTES:

- 1. GRASS DRAINAGE CHANNEL CROSS SECTION: 4" OF LOAM TO BE SEEDED WITH APPROVED SEED MIX. SEED TO BE LIGHTLY RAKED INTO LOAM TO ALLOW FOR PROPER SEED/SOIL
- 2. EROSION CONTROL BLANKET SHALL COVER ALL DRAINAGE CHANNELS AND BE INSTALLED AS PER MANUFACTURES' SPECIFICATIONS.
- 3. TURF REINFORCEMENT MAT (TRM) WILL BE USED FOR ANY SECTION OF THE CHANNEL THAT HAS A SHEAR STRESS GREATER THAN 1LB/FT^2. **ROLLMAX VMAX P550 TURF** REINFORCEMENT MAT OR APPROVED EQUAL MUST BE USED FOR INSTALLATION.
- INSTALL CHECK DAMS EVERY HUNDRED FEET IN DRAINAGE CHANNEL THAT HAS MORE THAN 5% SLOPE AND AT JOINTS IN THE GEOTEXTILE FABRIC. ANCHOR THE CHECK DAM TWO FEET INTO EITHER SIDE OF THE CHANNEL. SECURE THE FABRIC LAP NEAR THE CHECK DAM SO AS TO HINDER LAP SEPARATION.

TABLE 1A. DRAINAGE CHANNEL INSTALLATION TABLE

Drainage Channel	Sheer Stress [lbs/ft^2]	Lining
Upper 200 feet of Drainage Channel 2	7.8	Turf Reinforcement Mat
Lower Part of Drainage Channel 2	0.50	Grass
Upper 20 feet of Drainage Channel 3	10.87	Turf Reinforcement Mat
Last 130 feet of Drainage Channel 3	3.31	Turf Reinforcement Mat
First 130 feet of Drainage Channel 4	2.18	Turf Reinforcement Mat
Middle 30 feet of Drainage Channel 4	4.65	Turf Reinforcement Mat
Lower 90 feet of Drainage Channel 4	1.93	Turf Reinforcement Mat
Upper 30 feet of Drainage Channel 5	4.23	Turf Reinforcement Mat
Lower 300 feet of swale 5	0.28	Grass
First 180 feet of Upper Drainage Channel 6	0.25	Grass
180 feet to end of Upper Drainage Channel 6	0.94	Grass
460 feet to 950 feet of Upper Drainage Channel 6	0.81	Grass
Middle Drainage Channel 6 between proposed culverts	3.49	Turf Reinforcement Mat
Lower Drainage Channel 6	4.04	Turf Reinforcement Mat
Drainage Channel 7 first 40 feet and last 40 feet	0.98	Grass
Drainage Channel 7 middle 360 feet	0.22	Grass
Drainage Channel 8 first 200 feet	0.18	Grass
Drainage Channel 8 middle 150 feet	0.97	Grass
Drainage Channel 8 last 150 feet	2.29	Turf Reinforcement Mat
Drainage Channel 9 (roadside)	2.37	Turf Reinforcement Mat
Drainage Channel 10 first 150 feet	0.2	Grass
Drainage Channel 10 from 150 feet to 500 feet	0.71	Grass
Drainage Channel 10 from 500 feet to end	1.98	Turf Reinforcement Mat
Drainage Channel 11	1.07	Turf Reinforcement Mat
Drainage Channel 12	2.12	Turf Reinforcement Mat
Drainage Channel 13	1.09	Turf Reinforcement Mat
Drainage Channel 14	5.31	Turf Reinforcement Mat

10-20



ROCK CHECK DAM

WARE SOLAR

Prepared for:


MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

CIVIL DETAILS

PRELIMINARY-NOT FOR CONSTRUCTION

DATE: 09/03/2020 SHEET: 17

DRAINAGE CHANNEL




WIREBACKED WITH HAYBALE SILT FENCE


- WOVEN WIRE FENCE TO BE FASTENED SECURELY
- TO FENCE POSTS WITH WIRE TIES. GEOTEXTILE TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- WHEN TWO SECTIONS OF GEOTEXTILE ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED.


4. MAINTENANCE SHALL BE PERFORMED AS NOTED IN

- THE EROSION CONTROL PLAN. COLLECTED MATERIAL SHALL BE REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.
- 5. ALL SILT FENCE SHALL INCLUDE WIRE SUPPORT UNLESS INDICATED OTHERWISE.
- 6. WIREBACKED WITH HAYBALE SILT FENCE TO BE USED AS NEEDED.



6" SCH40 SUBDRAIN OUTLET






SAND FILTER AND SUB DRAIN DESIGN NOTES

- THE CONTRACTOR SHOULD ENSURE THAT CARE IS TAKEN DURING EXCAVATION, BY MECHANICAL MEANS, OF THE BOTTOM OF THE SAND
- FILTER AREAS TO PROMOTE ANY AVAILABLE INFILTRATION. THE CONTRACTOR SHALL NOT TO COMPACT OR SMEAR THE SOIL AT THE BOTTOM OF EXCAVATIONS, VEHICULAR TRAFFIC IS NOT ALLOWED
- WITHIN THE FOOTPRINT OF THE FOREBAY/RECHARGE AREA BOTTOM 3. CONTRACTOR TO INSTALL ORANGE SNOW FENCE AROUND THE FOREBAY/RECHARGE AREA AFTER INITIAL CONSTRUCTION/EXCAVATION OF THE BMP FOR PROTECTION OF THE AREAS DURING CONSTRUCTION
- SAND FILTERS SHALL ACT AS TEMPORARY SAND FILTER DURING
- CONSTRUCTION OF THE PROJECT.
- 5. SUBDRAINS SHALL BE THE LOW POINT OF THE SAND FILTER BOTTOMS

WIREBACKED WITH HAYBALE SILT FENCE



INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN ACCUMULATED TO 1/2 THE HEIGHT OF THE FABRIC OR MORE.

REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT

CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.

- 3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING
- 4. ALL ENDS OF THE SILT FENCE SHALL BE WRAPPED UPSLOPE SO THE ELEVATION OF THE BOTTOM OF FABRIC IS HIGHER THAN "PONDING HEIGHT".

SILT FENCE

GEOTEXTILE FABRIC

- $(\mathsf{1})$ FOR PIPES GREATER OR EQUAL TO 30", USE 1.5'. 2. THE CONTRACTOR SHALL PLACE RIP RAP, PULVERIZED TOPSOIL, SEED AND WOODFIBER BLANKET IMMEDIATELY AFTER PIPE IS INSTALLED, EXTEND AREA TO MATCH UNDISTURBED
- (3) DIMENSION "E" EQUALS INSIDE WIDTH OF APRON. 4. RIP RAP SHALL BE CLASS 3 SIZE UNLESS OTHERWISE NOTED ON PLANS.

RIP RAP


TABLE OF QUANITIES

CLASS III d₅₀=9"

SECTION B-B


- 1. FIBER ROLLS SHALL BE INSTALLED PRIOR TO UPSLOPE DISTURBANCE ACTIVITIES
- 2. FIBER ROLLS SHALL BE PREFABRICATED AND MADE FROM WEED FREE RICE STRAW, FLAX, OR A SIMILAR AGRICULTURAL MATERIAL BOUND INTO A TIGHT TUBULAR ROLL BY NETTING. USE A 6" [152mm° OR 12" [305mm° DIA. ROLL. 3. TRENCHES SHALL BE CREATED ALONG THE SLOPE OF THE PERIMETER. THE
- THE WIDTH SHOULD EQUAL THE ROLL DIAMETER, IN ORDER TO PROVIDE AREA TO BACKFILL THE TRENCH. 4. STAKE FIBER ROLLS INTO THE TRENCH. DRIVE STAKES AT THE END OF EACH FIBER ROLL AND SPACED 4 FEET [1.219m° MAXIMUM ON CENTER. USE WOOD STAKES WITH NOMINAL CLASSIFICATION OF 0.75 IN. [19mm° BY 0.75 IN.
- [19mm° AND A MINIMUM LENGTH OF 24 IN. [610mm° 5. ROLLS SHALL BE INSTALLED PERPENDICULAR TO WATER MOVEMENT, AND
- PARALLEL TO THE SLOPE CONTOUR. 6. TURN THE ENDS OF THE FIBER ROLLS UP SLOPE TO PREVENT RUNOFF FROM GOING AROUND THE ROLL. THE UPSLOPE POINT SHOULD BE A MINIMUM 6" HIGHER IN ELEVATION THAN THE LOW POINT.
- 7. IF MORE THAN ONE FIBER ROLL IS PLACED IN A ROW, THE ROLLS SHOULD BE OVERLAPPED A MINIMUM OF 6 INCHES [152mm°, NOT ABUTTED. 8. FIBER ROLLS ENCASED WITH PLASTIC NETTING ARE USED FOR A TEMPORARY APPLICATION ONLY AND SHOULD BE REMOVED FOLLOWING STABILIZATION. FIBER
- ROLLS USED IN A PERMANENT APPLICATION SHALL BE ENCASED WITH A BIODEGRADABLE MATERIAL AND MAY BE LEFT IN. 9. TEMPORARY INSTALLATIONS SHOULD ONLY BE REMOVED WHEN UP GRADIENT AREAS ARE STABILIZED PER GENERAL PERMIT REQUIREMENTS, AND/OR POLLUTANT SOURCES NO LONGER PRESENT A HAZARD. BUT, THEY SHOULD ALSO BE REMOVED BEFORE VEGETATION BECOMES TOO MATURE SO THAT THE
- 10. FIBER ROLLS MUST BE INSPECTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS FOR THE ASSOCIATED PROJECT TYPE AND RISK LEVEL. IT IS RECOMMENDED THAT AT A MINIMUM, THE BMPS BE INSPECTED WEEKLY, PRIOR TO FORECASTED RAIN EVENTS, DAILY DURING EXTENDED RAIN EVENTS, AND AFTER THE CONCLUSION OF RAIN EVENTS.

REMOVAL PROCESS DOES NOT DISTURB MORE SOIL AND VEGETATION THAN IS




- 12. REPAIR OR REPLACE SPLIT, TORN, UNRAVELING, OR SLUMPING FIBER ROLLS. 13. SEDIMENT THAT ACCUMULATES UPSLOPE OF THE BMP SHOULD BE PERIODICALLY REMOVED IN ORDER TO MAINTAIN BMP EFFECTIVENESS. SEDIMENT SHOULD BE REMOVED WHEN
- SEDIMENT ACCUMULATION REACHES ONE-THIRD THE DESIGNATED SEDIMENT STORAGE DEPTH. 14. RILLS OR GULLIES MAY BEGIN TO FORM FOLLOWING MAJOR STORM EVENTS WHERE RUNOFF HAS OVERTOPPED THE FIBER ROLLS. THESE RILLS OR GULLIES SHOULD BE PROMPTLY

SAND FILTER AND SUBDRAIN DETAIL



- FENCE AND GATE TYPE TO BE APPROVED BY OWNER PRIOR TO CONSTRUCTION
- STRUCTURAL DESIGN TO BE PROVIDED BY FENCE SUPPLIER
- DIMENSIONS AND INFORMATION SHOWN ABOVE ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS AND INFORMATION TO BE PROVIDED BY MANUFACTURER/SUPPLIER
- 4. FENCE/GATE TO BE 7.5' TALL, 6" WILDLIFE GAP AT THE BOTTOM, AND MUST BE DARK OR EARTH TONED COLOR.



- 1. FENCE AND GATE TYPE TO BE APPROVED BY OWNER PRIOR TO CONSTRUCTION 2. STRUCTURAL DESIGN TO BE PROVIDED BY FENCE SUPPLIER
- 3. DIMENSIONS AND INFORMATION SHOWN ABOVE ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS
- AND INFORMATION TO BE PROVIDED BY MANUFACTURER/SUPPLIER 4. FENCE/GATE TO BE 7.5' TALL, 6" WILDLIFE GAP AT THE BOTTOM, AND MUST BE DARK OR EARTH TONED COLOR.

PERIMETER CHAIN-LINK FENCE/GATE DETAIL

Westwood

(952) 937-5150 12701 Whitewater Drive, Suite 300 Minnetonka, MN 55343



westwoodps.com

Designed:		MP
Checked:		ΑC
Drawn:		MP
Drawn:		
Record Drawing	g by/date:	
Record Drawing Revisions: # DATE		
Revisions:		
Revisions:		
Revisions:		

Prepared for:



WARE SOLAR

MONSON TURNPIKE ROAD WARE, MA HAMPSHIRE COUNTY

CIVIL DETAILS

PRELIMINARY-NOT FOR CONSTRUCTION