

WAUPACA COUNTY HIGHWAY DEPARTMENT 2021 PLANNING FOR PROJECTS

Project Scope

The Waupaca County Highway System will be the premier highway system in Wisconsin, boasting roadways of the highest quality that provide the safest transportation for current and future generations. Construction projects must be balanced and coordinated with multiple maintenance projects. This plan is only exclusive to County Highway projects and is designed as a general tool for additional unforeseen County work, Town/Municipal projects along with WisDOT projects.

Description of Construction Projects:

CTH O – STH 22 to CTH OO, Town of Union - 1.89 miles

Crews replaced three box culverts in 2020. The roadway will be fully reconstructed and the first mat of asphalt placed in 2021 with the 2nd mat of asphalt planned for 2023.

Description of Paving Projects:

CTH I – USH 45 to Shawano County Line, Towns Larrabee and Matteson – 8.6 miles

This project consists of the final mat of asphalt to include shouldering and painting. This project will be one of the first asphalt paving projects on the County Trunk system in 2021.

CTH B – STH 49 to Drath Road, Towns of Scandinavia and St. Lawrence - 3.60 miles

This is a Reclaim, Shape and Pave project. Both layers of asphalt are planned to be completed prior to June 30, 2021.

CTH Q – STH 49 to Bartel Road, Town of Scandinavia - 3.2 miles

This is a Reclaim, Shape and Pave project. Reshape ditches, replace culverts, add some gravel (3" at most), reshape and add both mats of asphalt.

Description of Other Projects:

CTH O – CTH OO to Island Road, Town of Union – 2.3 miles

Approximately seven cross culverts to replace in-kind, ditch work to make culverts function until following year's project completion.

CTH O – Engineering/Permitting of two different culverts

Town of Bear Creek, located between Kutchenriter and Island Roads

Town of Little Wolf, located between Mountain Lake and Butternut Roads

CTH D – Polymer Overlay of Bridge deck

City of New London, located on CTH D, south of STH 54 approximately 800 feet

Chipsealing Projects:

CTH QQ from STH 54 to STH 22, CTH Q from CTH QQ to Round Lake Dr., CTH C from STH 110 to USH 45, CTH U from Waushara County Line to USH 10